

FACT SHEET

UPDATED: 07.03.23

ABOUT THE PROJECT

The Olivenhain Trunk Sewer project extends between I-5 and Lone Jack Road along Manchester Avenue and Escondido Creek in the Olivenhain community of Encinitas. The project will upsize 2,600 feet of sewer pipeline and line 54 manholes.

The existing 1970's sewer line extends roughly 4 miles on City roads, San Elijo Lagoon Conservancy land, County of San Diego land, and private property. The existing manholes along the sewer line have deteriorated over time. This allows water to infiltrate the sewer pipeline during heavy rain which can overwhelm the treatment system or potentially cause a spill.

Phase 1 completed sewer improvements within City right of way. Future phases will complete work outside City right of way, as easements are procured.

BENEFITS

- Lining manholes prevents rain runoff from entering sewer lines.
- Obtaining easements will ensure access to all sewer line components for inspections and maintenance.
- Increasing the size of the sewer line provides additional capacity.



Olivenhain Trunk Sewer Improvements Project (CC04J)



City of
ENCINITAS

505 South Vulcan Avenue
Encinitas, CA 92024
760.633.2600 | encinitasca.gov

UPCOMING MILESTONES

Phase 1: Construction on City right of way

- Construction completed: October 2021

Phase 1A: Lining Sewer Manholes via Temporary Construction Easement

- Construction began in February 2022 and was completed in May 2023. The Notice of Completion will go to City Council in Aug. 2023.

Phases 2 & 3 will require permanent easements. Their construction start dates will be determined once right of way has been secured.

**All dates are approximate and subject to change.*



PROJECT BUDGET

The cost for planning, design, and construction for Phase 1 was approx. \$11 M. The projects are fully funded by the Cardiff Sanitation District.

CONTACT US

For questions or concerns about the project, please contact Matt Widelski, Principal Engineer at: mwidelski@encinitasca.gov or 760-633-2862

PROJECT STATUS

Phase 1 of the project was completed in October 2021.

Phase 1A involved rehabilitating and lining of 42 manholes between El Camino Del Norte and Manchester Avenue. Design was finalized in February 2022 and Phase 1A construction began in late spring 2022 and was completed in August 2023.

Phases 2 & 3 require permanent easements so the dates cannot be determined until that has been secured. Finalizing appraisals and easements is ongoing.

This project supports the Community Planning focus area of the Strategic Plan to maintain safe and livable communities through well-maintained infrastructure and facilities.



City of
ENCINITAS

505 South Vulcan Avenue
Encinitas, CA 92024
760.633.2600 | encinitasca.gov